# FIRST FLOOR PLAN

NOTES :

1. ALL DIMENTION ARE GIVEN IN MILIMETRES UNLESS OTHERWISE MENTION.
2. DO NOT SCALE OUT ANY DIMENSIONS FROM THE DRAWING FOLLOW WRITTEN DIMENSION ONLY.
3. 100 WIDE 12 THICK PLYWOOD PELMET BOX WITH CURTAIN ROD SHALL BE PROVIDED FOR ALL OPENINGS (DOOR & WINDOWS).

PIPE SCHEDULE:–

| S.NO. | DESCRIPTION | SIZE |
|---|---|---|
| | PIPE DIA FROM WC TO VERTICAL STACK/MH. | 00ø uPVC |
| | PIPE DIA FROM FT TO VERTICAL STACK/GT. | 00ø uPVC |
| | PIPE DIA FROM FD TO FT | 50ø uPVC |
| | PIPE DIA FROM WB's FD TO FT | 75 00uPVC |

FOR SIZING OF VERTICAL WATER SUPPLY LINE, PLEASE REFER WATER SUPPLY SCHEMATIC DIAGRAM DWG.

LEGEND

| S.NO. | SYMBOL | DESCRIBTION | P.NO. |
|---|---|---|---|
| 1. | | 100mm CI VERTICAL SOIL PIPE | ① |
| 2. | | 100mm CI VERTICAL WASTE PIPE | ② |
| 3. | | COLD WATER PIPE D/N FROM OHT | ③ |
| 4. | | 100X100MM FLOOR TRAP | |
| 5. | | FLOOR CLEAN OUT PLUG(FCO) | |
| 6. | | 100X100MM URINAL TRAP | |
| 7. | | 75Ø RAIN WATER PIPE | 6a |

CLIENT:-
DIRECTORATE GENERAL
ASSAM RIFLES
SHILLONG

PROJECT :
**CONSTRUCTON OF TYPE-V QUARTER** FOR ASSAM RIFLES AT KOHIMA, NAGALAND

DRG TITLE :-
**FIRST FLOOR DRAINAGE SYSTEM**

DRAWING NO:- TYPEV–PL–02

SCALE :-

DATE 12.09.2017

**DRAWN BY:**

**CHECKED BY:**

PROJECT EXECUTING AGENCY :-
HINDUSTAN PREFAB LTD.
(A Govt. of India Enterprise)
Jangpura, New Delhi

**ASSOCIATES CONSULTANCY:**
Buildcon Solutions
HEAD OFFICE :- L-11,SARITA VIHAR,
NEW DELHI-76
TELE FAX :- 011 - 40506870
EMAIL-buildconsolutions@gmail.com