ANNEXURE-III

HINDUSTAN PREFAB LIMITED						
(A Govt. of India Enterprise)						
Name of Work: "Construction of 01 No Type-V Quarter for AR Bn at Kohima, Nagaland."						
BOQ FOR EARTH CUTTING AND FILLING						
Sl. No.	**Description**	**Qty**	**Unit**	**Rate (in Rs.)**	**Amount (in Rs.)**	**DSR Ref.**
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth.1.5m in width as well as 10 sqm on plan) including disposal ofexcavated earth, lead upto 50m and lift upto 1.5m, disposed earth tobe levelled and neatly dressed.earth to be levelled and neatly dressed.					
(a)	All kind of soil	875.00	Cum	129.35	113181.25	2.6.1
1b	Carriage of materials by mechanical transport including loading, unloading and stacking					
	earth within 5 kms lead	875.00	Cum	125.92	110180	1.1.2
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	0.00	Cum	83.80	0	2.25
3	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	7.00	sqm	482.00	3374	2.31
	TOTAL				**226735**	
	Add Cost Index @41%				92961	
	Total				**319697**	