



COLUMN LAYOUT PLAN.



FOUNDATION PLAN.



SECTION:-A-A.

FOOTING SCHEDULE

FOOTING MARK	L	B	D
F1	1500	1500	450
F2	2000	2000	450

WAYSIDE AMENITIES FOR  
BUDDHIST & RAMAYAN  
CIRCUITS UNDER SWADESH  
DARSHAN SCHEME


TENDER DRAWING

- THIS DRAWING IS THE COPYRIGHT OF THE CONSULTANTS AND MAY BE USED OR REPRODUCED ONLY WITH HIS PRIOR PERMISSION.
- GENERAL NOTES:-**
1. ALL DIMENSIONS ARE IN MM.
  2. DO NOT SCALE ANY DIMENSIONS.
  3. CONFIRM LOCATION OF WALLS WITH RELEVANT ARCH. DRGS.
  4. FOR R.C.C. WORK USE MIX M25 CONFORMING TO IS 456 : 2000 OR AS SPECIFIED IN RESPECTIVE DWG.
  5. THE REINFORCEMENT SHALL BE T.M.T. BARS HAVING YIELD. STRENGTH NOT LESS THAN 500 N/mm<sup>2</sup> AND CONFORMING TO I.S. 1786 – 2008.
  6. THE CLEAR COVER TO THE REINFORCEMENT SHALL BE AS FOLLOWS:-  
(a) FOUNDATION  
RAFT BOTTOM : 60 MM  
RAFT TOP & SIDE : 50 MM  
(b) COLUMNS : 40 MM  
(c) BEAMS (top & bottom): 25 MM side cover 25mm  
(d) SLABS : 20 MM  
(e) CHAJJAS/CONOPY : 20 MM  
(f) R.C.C. WALL : 25 MM
  10. THE LAPS IN BARS SHALL BE STAGGERED & AT ONE PLACE SHALL NOT BE MORE THAN 50 PERCENT.
  11. ----- INDICATES TOP BARS  
----- INDICATES BOTTOM BARS
  12. READ THIS DRAWING IN CONJUNCTION WITH RELEVANT ARCHITECTURAL DRAWINGS. ANY DISCREPANCY IF FOUND SHALL BE BROUGHT TO THE NOTICE OF CONSULTANT.
  13. ALL R C C TO BE MACHINE MIXED AND VIBRATED AND CURED THOROUGHLY AS PER I.S 456-LATEST.

REVISIONS			
NO.	REVISION DETAIL	DATE	SIGNATURE

SITE LOCATION	
SITE -2A	: LUCKNOW-AYODHYA ROAD
SITE -2B	: AYODHYA-LUCKNOW ROAD

CLIENT	
WAYSIDE AMENITIES FOR BUDDHIST & RAMAYAN CIRCUITS UNDER SWADESH DARSHAN SCHEME	

EXECUTING AGENCY	
 HINDUSTAN PREFAB LTD.	

TITLE	
TOILET BLOCK COLUMN LAYOUT,FOUNDATION PLAN & DETAILS.	

DEALT	LALIT TIWARI	DATE 18-12-18
CHECKED BY	RM	SCALE
DRG NO.	ST- 07	

ARCHITECT	
M/S ARCHITECT YETINDER MATHUR U-21 GREEN PARK EXTENSION NEW DELHI 764 SECTOR8B CHANDIGARH	